

2024 Multifamily Checklist Summary of Changes

Detailed Summary of Changes for the 2024 Multifamily Checklist:

| 2021 MF Checklist Version | 2024 MF Checklist Version | |
|--|--|--|
| Section 1: Requirements | | |
| 3-Star Requirements | | |
| 1-7: Building performance modeled ERI of 58 or less OR BPF of 0.55 or less; OR achieves prescriptive credits on the 2018 WSEC R406.3 (5.5 credits) or C406.1 (11 credits) tables (Credits 3-1, 3-2, 3-3, or 3-4) | Removed requirement | |
| | Added requirement 1-13: Choose 1 out of the 7 Carbon Reduction Prescriptive Credits (Credits 7-1 through 7-7); OR complete Performance pathway (Credit 7-8) | |
| 4-Star Requirements | | |
| 1-18: Building performance modeled ERI of 55 or less OR BPF of 0.52 or less; OR achieves prescriptive credits on the 2018 WSEC R406.3 (6 credits) or C406.1 (16 credits) tables (Credits 3-1, 3-2, 3-3, or 3-4) | Removed requirement | |
| 1-19: Design for solar readiness | Removed requirement | |
| 1-25: Use at least one material or product with an HPD or EPD (credit 4-23 or 5-88) | Removed requirement | |
| 1-26: Achieve minimum recycling rate of 50% by weight (credit 5-16) | Removed requirement | |
| | Added requirement 1-24: Choose 3 out of the 7 Carbon Reduction Prescriptive Credits (Credits 7-1 through 7-7); OR complete Performance pathway (Credit 7-8) | |
| 5-Star Requirements | | |
| 1-32: Building performance modeled ERI of 47 or less OR BPF of 0.48 or less; OR achieves prescriptive credits on the 2018 WSEC R406.3 (7 credits) or C406.1 (28 credits) tables (Credits 3-1, 3-2, 3-3, or 3-4) | 1-29: Building performance modeled ERI of 47 or less OR BPF of <u>0.43</u> or less; OR achieves prescriptive credits on the 2021 WSEC R406.3 (<u>8</u> credits) or C406.1 (<u>50</u> credits) tables (Credits 3-1, 3-2, 3-3, or 3-4) | |
| 1-36: Achieve a minimum recycling rate of 75% | Removed requirement | |
| of waste by weight Section 2: Site & Water | | |
| 2-51: Install ALL kitchen faucets with 1.8gpm or less | 2-51: Install ALL kitchen faucets with <u>1.75gpm</u> or less | |
| ICSS | UI IC33 | |



| Section 3: Energy Efficiency | |
|---|--|
| Section 3: Energy Efficiency | 24.5 |
| 3-1: Document a building performance ERI of | 3-1: Document a building performance ERI of |
| 58 or less, before PV solar generation is | 55 or less |
| included | Edited points from 30, 50, or 80 to 30, 45, 60, 75, or 90 |
| 3-2: Document building improvements beyond | 3-2: Document building improvements beyond |
| 2018 WSEC using a prescriptive approach by | 2021 WSEC using a prescriptive approach by |
| earning at least 5.5 credits on R406.3 table, less | earning at least <u>7.0</u> credits on R406.3 table |
| than 50% of points may come from PV solar | Edited points from 30, 50, or 80 to 30, 45, 60, |
| generation | 75, or 90 |
| 3-3: Document a building performance factor of 0.55 or less | 3-3: Document a building performance factor of 0.49 or less |
| | Edited points from 30, 60, 90 to 15, 30, 45, 60, |
| | 75, or 90 |
| 3-4: Document building improvements beyond | 3-4: Document building improvements beyond |
| 2018 WSEC using a prescriptive approach by | 2021 WSEC using a prescriptive approach by |
| earning at least 11 credits the C406.1 table, less | earning at least <u>44</u> credits on the C406.1 table |
| than 50% of points may come from PV solar | |
| generation | |
| Section 5: Materials Efficiency | |
| 5-16: Send at least 90% of jobsite waste (by | Moved credit to Section 7 and edited credit: |
| weight, excluding concrete, brick, and asphalt) | Send at least 90% of jobsite waste (by weight, |
| to a commingled recycling facility with a | excluding concrete, brick, and asphalt) to a |
| minimum of 50% diversion rate (see Built | commingled recycling facility with a minimum |
| Green Recycling Guidelines); 50% diversion rate | of 50% diversion rate |
| (8pts), 75% (12pts), 90% (15pts) | |
| 5-24: Use building-salvaged lumber, minimum | Moved credit to Section 7 |
| 200 board feet | Edited points from 1-8 to 4, 8, 12, or 16 |
| 5-31: Use factory-framed wall panels (panelized | Edited points from 6-8 to 4 or 8 |
| wall construction), e.g. SIPs, ICFs, CLT | |
| 5-33: Use advanced wall framing – 24-inch OC, | Edited points from 2 to 5 |
| with double top plate | |
| 5-37: For all foundations, retaining and | Moved credit to Section 7 |
| structural walls, use supplementary | |
| cementitious materials for 25-50% by weight of | |
| cementitious materials for all concrete; 25% (3 | |
| pts) and 50% (6 pts) (pavement excluded) | |
| 5-88: Use materials with Environmental Product | Moved credit to Section 7 |
| Declaration (EPD) (1 pt per EPD) | Edited points from 1-10 to 2-16 |
| 5-90: Calculate the embodied carbon of the | Moved credit to Section 7 (credits 7-7 and 7-8) |
| new building OR calculate an embodied carbon | |
| baseline and show at least a 10% reduction | |
| Section 6: Equity & Social Justice | |



2024 Multifamily Checklist Summary of Changes

| 6-9: Develop a project-specific ESJ plan clearly | Increased points from 3 to 5 |
|--|--|
| indicating equity objectives and actions; | |
| identifying priority actions | |
| 6-30: Provide subsidized bus passes (25% or | Reduced points from 6-10 to 3 or 6 |
| 50% subsidized) | |
| Section 7: Carbon Reduction (new section) | |
| 5-11: Engage a salvage professional to conduct | Moved 5-11 credit to 7-1: Engage a salvage |
| a salvage assessment of buildings planned for | professional to conduct a salvage assessment |
| removal | of buildings planned for removal |
| | Increased points from 3 to 6 |
| 5-16: Send at least 90% of jobsite waste (by | Moved credit to Section 7 |
| weight, excluding concrete, brick, and asphalt) | Edited credit: Send at least 90% of jobsite |
| to a commingled recycling facility with a | waste (by weight, excluding concrete, brick, and |
| minimum of 50% diversion rate (see Built | asphalt) to a commingled recycling facility with |
| Green Recycling Guidelines); 50% diversion rate | a minimum of 50% diversion rate |
| (8pts), 75% (12pts), 90% (15pts) | |
| 5-24: Use building-salvaged lumber, minimum | Moved credit to Section 7 |
| 200 board feet | Edited points from 1-8 to 4, 8, 12, or 16 |
| 5-37: For all foundations, retaining and | Moved credit to Section 7 |
| structural walls, use supplementary | |
| cementitious materials for 25-50% by weight of | |
| cementitious materials for all concrete; 25% (3 | |
| pts) and 50% (6 pts) (pavement excluded) | |
| | Added 7-5: For all concrete pavements, use |
| | supplementary cementitious materials for 25- |
| | 50% by weight of cementitious materials for all |
| | concrete; 3pts for 25% and 6pts for 50% |
| 5-88: Use materials with Environmental Product | Moved credit to Section 7 |
| Declaration (EPD) (1 pt per EPD) | Edited points from 1-10 to 2-16 |
| 5-90: Calculate the embodied carbon of the | Moved credit to Section 7 (credits 7-7 and 7-8) |
| new building OR calculate an embodied carbon | |
| baseline and show at least a 10% reduction | |